



ENGLEWOOD WATER DISTRICT

201 Selma Ave
Englewood, FL 34223
(941) 474-3217

To: Prospective Bidders
Date: May 22, 2020
Re: **Addendum #2** to RFB 2020-117 WWTP #4 Rehabilitation Painting & Coating
Bid Due Date and Time: 2:15 p.m. (EST), May 27, 2020

Bidders are notified that this Addendum will be made part of the bid documents. The intent of the Addendum is to add to, modify, or clarify the documents. Should any of these items have an effect on price, such changes shall be included in the bid price. These items have the same force and effect as if contained in the original documents.

Questions and Answers

- Q1. What is the estimated construction cost for this project?
A1. *The estimated cost for this project is \$155,000.*
- Q2. Can blast media be disposed of on-site?
A2. *Yes, the blast media can be disposed of on site. Staff will indicate where media is to be placed during the pre-construction meeting.*
- Q3. Will the exterior piping associated with the tank require painting?
A3. *Yes, the exterior piping shall be included in the pricing for both Item B – PREP 7 COAT EXTERIOR SURFACES (BASE BID) and Alternate Item #1. Please see Addendum 3, Revised Bid form on Page 3 below. **This revised bid form replaces the bid form (page 28) in the solicitation package.***
- Q4. There is existing caulking located at the bottom weld seam inside the tank. Will re-caulking this weld seam be required? If so, with what product?
A4. *The existing caulking shall be removed prior to coating the structure. The District is awaiting an answer from the original plant supplier whether or not this caulking is required. It has been added to the Bid Form as Alternate #3. If it is deemed necessary, the contractor shall use a polysulfide sealant such as Thiokol 2235 along the bottom weld seam inside the tank. After the application of the coating system, apply Thiokol 2235, in accordance with the manufacturer's latest written recommendations.*

- Q5. Is the contractor required to remove and replace the stainless steel weir plates on launder trough? If so, will new nuts and bolts be required?
- A5. *The contractor is required to remove and replace the stainless steel weir plates on the launder trough. The contractor may reuse the existing hardware that they removed. Any hardware that is unable to be reused or misplaced, shall be replaced by the contractor. Any new hardware shall be the same or equal as to what was previously installed.*
- Q6. Will open air dry abrasive blasting be permitted? Or will wet abrasive blasting be required?
- A6. *Either option will be permitted as long as the contractor complies with all OSHA regulations.*

Bidders are required to acknowledge receipt of this addendum in their bid forms.

Bee Ling Wheaton,
Contracts & Procurement Specialist

PLEASE SEE REVISED BID FORM ON PAGE 3 BELOW

RFB 2020-117 ADDENDUM 2 - REVISED BID FORM – USE THIS FORM INSTEAD

ITEM	DESCRIPTION	QTY	UNIT PRICE	AMOUNT
A.	MOBILIZATION & DEMOBILIZATION: Item includes all labor and equipment required to deliver, store, protect paint and claning supplies, supply and erect scaffolding, mechanical lifts, hoists; all costs for bonds and insurance and port-o-lets for the life of the project; all labor and equipment required to clean, remove or dispose of all waste, materials, tools, scaffolding and return the project site to a good condition. Half of the lump sum cost can be requested at the beginning of the project. The remaining half can be claimed after demobilization is complete and the paint supplier has provided warranty on the project.	1	LUMP SUM	\$ _____
B.	PREP & COAT EXTERIOR SURFACES (BASE BID): Item includes all labor, equipment, and materials to prep and coat all exterior and non-immersion surfaces for Treatment Plant #4 per the paint supplier recommendations and these specifications. This includes all exterior piping associated with Treatment Plant #4.	1	LUMP SUM	\$ _____
C.	PREP & COAT INTERIOR & CATWALK SURFACES: Item includes all labor, equipment, and materials to prep and coat all submerged or intermittently submerged surfaces for Treatment Plant #4 per the paint supplier recommendations and these specifications.	1	LUMP SUM	\$ _____
D.	PREP & COAT EXTERIOR CONCRETE SURFACES (BASE BID): Item includes all labor, equipment, and materials to prep and coat all exterior concrete surfaces for Treatment Plant #4 per the paint supplier recommendations and these specifications.	1	LUMP SUM	\$ _____

TOTAL BID (A+B+C+D) \$ _____

TOTAL BID (WRITTEN OR PRINTED): _____

ALTERNATE BID ITEMS:				
1	PREP & COAT EXTERIOR/NON-IMMERSION SURFACES (ALTERNATE #1): Item includes all labor, equipment, and materials to prep and coat all exterior and non-immersion surfaces for Treatment Plant #4 per the paint supplier recommendations and these specifications. This includes all exterior piping associated with Treatment Plant #4.	1	LUMP SUM	\$ _____
2	PREP & COAT EXTERIOR CONCRETE SURFACES (ALTERNATE #2): Item includes all labor, equipment, and materials to prep and coat all exterior concrete surfaces for Treatment Plant #4 per the paint supplier recommendations and these specifications.	1	LUMP SUM	\$ _____
3	PREP 7 APPLY SEALANT TO INTERIOR WELD SEAM: Items includes all labor, equipment and materials to prep and install polysulfide sealant along the bottom weld seam inside the tank per manufacturer's recommendations.	1	LUMP SUM	\$ _____